

25



Corsicana Adult Probation  
 Corsicana, TX

5/16/22  
 Estimate # 4895

1. Remove and dispose of approx. 3,000 sqft. 2 layer roofing system down to metal deck
2. Inspect existing metal deck; any bad deck will be time and material additional charge
3. Furnish and install insulation needed to bring roof elevation to same elevation other roofs that tie into
4. Furnish and install new MB Base sheet atop insulation
5. Furnish and install new modified bitumen roofing system to manufacturers specs
6. Furnish and install all flashings needed for weather tight seal
7. Re-flash parapet walls
8. Furnish and install white granules at all bleeds and seams to prevent UV breakdown and for uniform color overall
9. Remove and dispose of approx. 100' box gutter and replace with new at no charge
10. Three (3) year limited workmanship warranty
11. Ten (10) year cap sheet manufacturer warranty

**Total \$50,000**

**Signature** \_\_\_\_\_ **Date:** \_\_\_\_\_

Upon signature, this estimate becomes a legal and binding contract for stated work to be performed.

General Note: Owner/General Contractor is advised that Ennis Roofing LLC reserves the right to file a Mechanic and Materialman Lien on the property as well as on all improvements and fixtures to secure payment for the cost of the project.

Thank you for giving a veteran/woman owned company the opportunity for your business. We are backed by The Good Contractors List with \$10,000 guarantee on workmanship. This estimate is good for 15 days.